

Validate

Print

Help

**Percentage BoQ**

Tender Inviting Authority: CEO, ASCDCL, AURANGABAD

Name of Work: Conservation and Restoration of Barapulla Gate

Contract No: ASCDCL/EE/WW/2019/ DATE

Bidder Name :						
<b>PRICE SCHEDULE</b>						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Conveying materials obtained from road cutting including all lifts, laying in layers of 20cm to 30cm. breaking clods, dressing to the required lines, curves, grades and section, watering and compacting to not less than 97% of standard Proctor density for a lead of over 50m. to 300m. inclusive from the site of excavation to the site of deposition as directed. SSR 18-19 ,2.25	90.00	Cum	345.31	<b>31077.95</b>	INR Thirty One Thousand & Seventy Seven and Paise Ninety Five Only
2	CAREFULLY REMOVAL OF GRASS, SCRAPING BRICK,STONE SURFACES BY CHEMICALS ,required oils and cleaning with jet spray etc --AS DIRECTED. ( non DSR - RA attached )	420.00	Sqm	1129.203	<b>474265.26</b>	INR Four Lakh Seventy Four Thousand Two Hundred & Sixty Five and Paise Twenty Six Only
3	Cutting down trees including trunks and branches with girths above 30cm to 60cm and stacking the materials neatly with all lifts and lead of 1000m as directed and earth filling in the depression / pit if any. SSR 18-19 ,2.01	7.00	No	387.95	<b>2715.62</b>	INR Two Thousand Seven Hundred & Fifteen and Paise Sixty One Only
4	Excavation for foundation in earth, soils of all types, sand,gravel and soft murum, including removing the excavated material upto a distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift from 1.5m to 3.0m) By Mechanical Means SSR 18-19 ,21.04	303.10	Cum	392.49	<b>118964.63</b>	INR One Lakh Eighteen Thousand Nine Hundred & Sixty Four and Paise Sixty Three Only
5	Excavation for foundation in hard murum including removing the excavated material upto distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 SSR 18-19 ,21.06	39.53	Cum	370.47	<b>14643.00</b>	INR Fourteen Thousand Six Hundred & Forty Three Only
6	Dismantling brick masonry in lime or cement mortar and stacking the materials as directed with all leads, lifts etc. SSR 18-19 ,46.09	130.50	Cum	455.40	<b>59430.09</b>	INR Fifty Nine Thousand Four Hundred & Thirty and Paise Nine Only
7	P/C 1ST CLASS BRICK MASONARY [1:3] LIME MORTER WITH ORGANIC ADHESIVE-ETC ( non DSR - RA attached )	298.50	Cum	8616.71	<b>2572087.34</b>	INR Twenty Five Lakh Seventy Two Thousand & Eighty Seven and Paise Thirty Four Only
8	Dismantling stone masonry in lime or cement mortar including stacking the materials as directed with all leads, lifts etc. SSR 18-19 ,46.11	141.00	Cum	488.96	<b>68942.66</b>	INR Sixty Eight Thousand Nine Hundred & Forty Two and Paise Sixty Five Only

9	Scaling off deteriorated stone ( non DSR - RA attached )	10.00	Sqm	483.00	<b>4830.00</b>	INR Four Thousand Eight Hundred & Thirty Only
10	P/C UCR STONE MASONARY FOR SUPERSTRUCTURE [1:3] LIME MORTER WITH ORGANIC ADHESIVE--ETC ( non DSR - RA attached )	256.13	Cum	5730.93	<b>1467834.45</b>	INR Fourteen Lakh Sixty Seven Thousand Eight Hundred & Thirty Four and Paise Forty Five Only
11	P/C 1ST CLASS COURSED/ASHLAR STONE MASONARY FOR SUPERSTRUCTURE [1:3] LIME MORTER WITH ORGANIC ADHESIVE--ETC ( non DSR - RA attached )	1.00	Cum	11081.13	<b>11081.13</b>	INR Eleven Thousand & Eighty One and Paise Thirteen Only
12	Providing and applying Wacker Chemical ( water base antifungal silicon treatment ) on manglore tiles or stone surface. stone consolidation ( Pune DSR 18-19 -14480 AK-63.15 -2 , Page no.203)	265.00	Sqm	503.28	<b>133369.20</b>	INR One Lakh Thirty Three Thousand Three Hundred & Sixty Nine and Paise Twenty Only
13	Removing the existing cement/lime plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. complete. SSR 18-19 ,32.33	640.00	Sqm	244.65	<b>156578.88</b>	INR One Lakh Fifty Six Thousand Five Hundred & Seventy Eight and Paise Eighty Eight Only
14	P/A 25 MM THK.LIME MORTER PLASTER[1:2] WITH ORGANIC ADHESIVE--ETC ( non DSR - RA attached )	202.50	Sqm	1193.07	<b>241597.16</b>	INR Two Lakh Forty One Thousand Five Hundred & Ninety Seven and Paise Sixteen Only
15	P/A 12 MM THK.LIME MORTER PLASTER[1:2] WITH ORGANIC ADHESIVE--ETC ( non DSR - RA attached )	202.50	Sqm	757.60	<b>153413.43</b>	INR One Lakh Fifty Three Thousand Four Hundred & Thirteen and Paise Forty Three Only
16	P/A PURE LIME FINISH PLASTER WITH ORGANIC ADHESIVE--ETC ( non DSR - RA attached )	365.00	Sqm	731.53	<b>267010.06</b>	INR Two Lakh Sixty Seven Thousand & Ten and Paise Six Only
17	TWO COATS LIME WASH PAINTING WITH NATURAL ORGANIC BINDERS--ETC. ( non DSR - RA attached )	365.00	Sqm	622.65	<b>227267.25</b>	INR Two Lakh Twenty Seven Thousand Two Hundred & Sixty Seven and Paise Twenty Five Only
18	P/A LIME MORTER [1:3] POINTING--ETC. ( non DSR - RA attached )	152.60	Sqm	506.45	<b>77284.06</b>	INR Seventy Seven Thousand Two Hundred & Eighty Four and Paise Six Only
19	Removing the tar or coba and disposing of the material as directed etc. complete. SSR 18-19 ,31.08	60.00	Sqm	125.17	<b>7510.29</b>	INR Seven Thousand Five Hundred & Ten and Paise Twenty Nine Only
20	P/L WATERPROOFING TREATMENT USING BRICK BATS [1:2] LIME MORTER WITH ORGANIC BINDERS--ETC ( non DSR - RA attached )	18.00	Cum	7274.94	<b>130948.92</b>	INR One Lakh Thirty Thousand Nine Hundred & Forty Eight and Paise Ninety Two Only
21	Providing antitermite treatment to the wooden frames of doors/windows of the existing building as per I.S. 6313 (Part-III) by drilling 6mm dia. holes at four corners on one side and four corners on other side at a downward angle of about 45 degree at the junction of wood work and masonary and injecting 150 ml. of chlorodane 5% W.C. and sealing by filling putty etc. complete covering 2 years guarantee on bond paper. SSR 18-19 ,21.26	1.00	No	54.52	<b>54.52</b>	INR Fifty Four and Paise Fifty Two Only

22	Providing and applying Wax polish to the old wood work including knotting, preparing the surface, scaffolding etc. complete as directed SSR 18-19 ,34.04	19.50	Sqm	34.60	<b>674.71</b>	INR Six Hundred & Seventy Four and Paise Seventy One Only
23	Providing and applying melamine polish of required finish to the wood work by spray machine including knotting and preparing the even surface by scraping, applying French polish , scaffolding if required etc. complete. Note:The work to be executed on prior approval of Superintending Engineer will be necessary. SSR 18-19 ,34.09	19.50	Sqm	631.20	<b>12308.34</b>	INR Twelve Thousand Three Hundred & Eight and Paise Thirty Four Only
24	Providing and fabricating structural steel work in rolled sections like joists, channels, angles, tees etc. as per detailed design and drawings or as directed including cutting, fabricating, hoisting, erecting, fixing in position making riveted / bolted /welded connections without connecting plates, braces etc. and including one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade etc. complete. SSR 18-19 ,23.01	0.50	MT	74458.18	<b>37229.09</b>	INR Thirty Seven Thousand Two Hundred & Twenty Nine and Paise Nine Only
25	GROUTING CRACKS,FILLING VOIDS AND FISSURES ON WALL WITH [1:2] LIME MORTER--ETC ( non DSR - RA attached )	20.00	Sqm	433.08	<b>8661.55</b>	INR Eight Thousand Six Hundred & Sixty One and Paise Fifty Five Only
26	PROVIDING SOIL BAGS FOR SUPPORTS-- ETC ( non DSR - RA attached )	500.00	No.	23.10	<b>11550.00</b>	INR Eleven Thousand Five Hundred & Fifty Only
27	P/ LAYING LIME CONCRETE M15 FOR PCC --ETC ( non DSR - RA attached )	15.00	Cum	8927.29	<b>133909.29</b>	INR One Lakh Thirty Three Thousand Nine Hundred & Nine and Paise Twenty Nine Only
28	Providing antitermite treatment around the periphery of the existing building as per I.S. 6313 (Part-III) by excavating trenches of 20cm width and exposing the sides of columns and plinth beams upto a depth of 300mm and injecting one percent of chlorodane emulsion concentrate at the rate of 2.25 litres per Rmt and refilling the trenches etc. complete covering 2 years guarantee on bond paper. SSR 18-19 ,21.29	100.00	Rmg	50.33	<b>5032.80</b>	INR Five Thousand & Thirty Two and Paise Eighty Only
29	Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete. SSR 18-19 ,21.38	16.09	Cum	1004.84	<b>16165.42</b>	INR Sixteen Thousand One Hundred & Sixty Five and Paise Forty Two Only
30	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm including watering and compaction etc. complete. SSR 18-19 ,31.37	16.09	Cum	395.99	<b>6370.53</b>	INR Six Thousand Three Hundred & Seventy and Paise Fifty Three Only

31	Basalt stone Paving in lime Mortar - Providing and Laying Newasa Stone for paving and thread risers in cement mortar of 150 mm thick (Two line dressed stone 0.45x0.30x0.125 to 0.15 and not less than 0.30x0.30x0.15 Mtrs cut in shape and two adjacent sides Stone flooring in Basalt to be dressed, from Newasa, Dist Ahmednagar) in plain/diamond pattern on a bed of 1:4 C.M. over 150mm thick lime concrete , and filling the gap in 1:2 Mortar etc, complete) STONE DRESSING IN TICHIV STYLE Pune DSR 18-19 -14480 AK-63.27 , Page no.203)	75.00	Sqm	7197.56	539817.12	INR Five Lakh Thirty Nine Thousand Eight Hundred & Seventeen and Paise Twelve Only
32	Providing and fixing 90 cm x 60 cm Granite plate engraving 10 cm. height letter, figures including painting the letters/figures with approved colour and shade complete SSR 18-19 ,44.12	2.00	No.	10321.43	20642.87	INR Twenty Thousand Six Hundred & Forty Two and Paise Eighty Seven Only
33	Stitching of cracks- Providing and fixing in position TMT FE 500, 32 mm dia dowel bars precoated with anticorrosive epoxy paint of required Dia. 60 cms. Long and at 30.00 cm. C/C and wherever directed including handling, straightening, necessary cutting supported by TMT FE 500, chairs with proper alignment by using properly designed assembly of Bulkheads lubricating half length with bituminous paint as directed etc. complete. SSR 18-19 ,5.14	15.00	No.	331.33	4969.89	INR Four Thousand Nine Hundred & Sixty Nine and Paise Eighty Nine Only
34	Providing and fixing of <b>water spout in Stone</b> for draining of terrace water , As per Architectural Drawing and Design . Spout of Sizes <b>Max . Length 900mm. As per market rate</b>	4.00	No.	12000.00	48000.00	INR Forty Eight Thousand Only
35	Providing and fixing mild steel grill gate as per the detailed drawing including hinges, locking arrangements and painting in three coats of oil paint of approved colour and shade etc. complete.(weight 18 kg. to 20 kg. Per Sq.m.) Spec.No.: As directed by Engineer- in-charge. SSR 18-19 ,23.09	12.00	Sqm	1541.30	18495.54	INR Eighteen Thousand Four Hundred & Ninety Five and Paise Fifty Four Only
36	Providing sills of polished Kadappa stone 25mm to 30mm thick, on a bed of 1:4 cement mortar including cement float, filling joints with slurry, curing polishing and cleaning etc. complete. SSR 18-19 ,33.20	16.25	Sqm	908.46	14762.55	INR Fourteen Thousand Seven Hundred & Sixty Two and Paise Fifty Five Only
37	<b>Landscaping work(job work)</b>	1.00	Lumsum	54645.12	141989.91	INR One Lakh Forty One Thousand Nine Hundred & Eighty Nine and Paise Ninety One Only
38	<b>Testing Charges</b>	1.00	Lumsum	67520.00	65320.00	INR Sixty Five Thousand Three Hundred & Twenty Only
39	<b>Royalty Charges</b>	1.00	Lumsum	44515.61	43654.06	INR Forty Three Thousand Six Hundred & Fifty Four and Paise Six Only
<b>Total in Figures</b>					<b>7350459.56</b>	INR Seventy Three Lakh Fifty Thousand Four Hundred & Fifty Six Only
<b>Quoted Rate in Figures</b>			<b>Select</b>		<b>0.0000</b>	INR Zero Only
<b>Quoted Rate in Words</b>			<b>INR Zero Only</b>			