

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority: CEO, ASCDCL, AURANGABAD

Name of Work: Conservation and Restoration of Naubat Gate

Contract No: ASCDCL/EE/WW/2019/ DATE

Bidder Name :						
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	CLEANING - Conveying materials obtained from road cutting including all lifts, laying in layers of 20cm to 30cm. breaking clods, dressing to the required lines, curves, grades and section, watering and compacting to not less than 97% of standard Proctor density for a lead of over 50m.to 300m. inclusive from the site of excavation to the site of deposition as directed. SSR 18-19 ,2.25	24.00	Cum	345.31	8287.45	INR Eight Thousand Two Hundred & Eighty Seven and Paise Forty Five Only
2	CAREFULLY REMOVAL OF GRASS, SCRAPING BRICK,STONE SURFACES BY CHEMICALS--AS DIRECTED. (non DSR - RA attached)	200.00	Sqm	1129.20	225840.60	INR Two Lakh Twenty Five Thousand Eight Hundred & Forty and Paise Sixty Only
3	Cutting down trees including trunks and branches with girths above 30cm to 60cm and stacking the materials neatly with all lifts and lead of 1000m as directed and earth filling in the depression / pit if any. SSR 18-19 ,2.01	4.00	No	387.95	1551.78	INR One Thousand Five Hundred & Fifty One and Paise Seventy Eight Only
4	Dismantling brick masonry in lime or cement mortar and stacking the materils as directed with all leads, lifts etc. SSR 18-19 ,46.09	2.00	Cum	455.40	910.81	INR Nine Hundred & Ten and Paise Eighty One Only
5	P/C IST CLASS BRICK MASONARY [1:3] LIME MORTER WITH ORGANIC ADHESIVE--ETC (non DSR - RA attached)	3.00	Cum	8616.71	25850.12	INR Twenty Five Thousand Eight Hundred & Fifty and Paise Twelve Only
6	Dismantling stone masonry in lime or cement mortar including stacking the materils as directed with all leads, lifts etc. SSR 18-19 ,46.11	24.00	Cum	488.96	11734.92	INR Eleven Thousand Seven Hundred & Thirty Four and Paise Ninety Two Only
7	Scaling off deteriorated stone (non DSR - RA attached)	100.00	Sqm	483.00	48300.00	INR Forty Eight Thousand Three Hundred Only
8	P/C UCR STONE MASONARY FOR SUPERSTRUCTURE [1:3] LIME MORTER WITH ORGANIC ADHESIVE--ETC (non DSR - RA attached)	28.00	Cum	5730.93	160466.04	INR One Lakh Sixty Thousand Four Hundred & Sixty Six and Paise Four Only
9	P/C IST CLASS COURSED/ASHLAR STONE MASONARY FOR SUPERSTRUCTURE [1:3] LIME MORTER WITH ORGANIC ADHESIVE--ETC (non DSR - RA attached)	2.00	Cum	11081.13	22162.26	INR Twenty Two Thousand One Hundred & Sixty Two and Paise Twenty Six Only
10	Providing and applying Wacker Chemical (water base antifungal silicon treatment)on manglore tiles or stone surface and stone consolidation (Pune DSR 18-19 -14480 AK-63.15 -2 , Page no.203)	240.00	Sqm	503.28	120787.20	INR One Lakh Twenty Thousand Seven Hundred & Eighty Seven and Paise Twenty Only

11	Removing the existing cement/lime plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. complete. SSR 18-19 ,32.33	116.00	Sqm	244.65	28379.92	INR Twenty Eight Thousand Three Hundred & Seventy Nine and Paise Ninety Two Only
12	P/A 12 MM THK.LIME MORTER PLASTER[1:2] WITH ORGANIC ADHESIVE--ETC (non DSR - RA attached)	80.00	Sqm	757.5972	60607.78	INR Sixty Thousand Six Hundred & Seven and Paise Seventy Eight Only
13	P/A 25 MM THK.LIME MORTER PLASTER[1:2] WITH ORGANIC ADHESIVE--ETC (non DSR - RA attached)	50.00	Sqm	1193.0724	59653.62	INR Fifty Nine Thousand Six Hundred & Fifty Three and Paise Sixty Two Only
14	P/A PURE LIME FINISH PLASTER WITH ORGANIC ADHESIVE--ETC (non DSR - RA attached)	100.00	Sqm	731.5344	73153.44	INR Seventy Three Thousand One Hundred & Fifty Three and Paise Forty Four Only
15	TWO COATS LIME WASH PAINTING WITH NATURAL ORGANIC BINDERS--ETC. (non DSR - RA attached)	230.00	Sqm	622.65	143209.50	INR One Lakh Forty Three Thousand Two Hundred & Nine and Paise Fifty Only
16	P/A LIME MORTER [1:3] POINTING--ETC. (non DSR - RA attached)	240.00	Sqm	506.4486	121547.66	INR One Lakh Twenty One Thousand Five Hundred & Forty Seven and Paise Sixty Six Only
17	Removing the tar or coba and disposing of the material as directed etc. complete. SSR 18-19 ,31.08	320.00	Sqm	125.17	40054.88	INR Forty Thousand & Fifty Four and Paise Eighty Eight Only
18	P/L WATERPROOFING TREATMENT USING BRICK BATS [1:2] LIME MORTER WITH ORGANIC BINDERS--ETC (non DSR - RA attached)	48.80	Cum	7274.94	355017.07	INR Three Lakh Fifty Five Thousand & Seventeen and Paise Seven Only
19	GROUTING CRACKS,FILLING VOIDS AND FISSURES ON WALL WITH [1:2] LIME MORTER--ETC (non DSR - RA attached)	8.00	Sqm	433.0776	3464.62	INR Three Thousand Four Hundred & Sixty Four and Paise Sixty Two Only
20	PROVIDING SOIL BAGS FOR SUPPORTS--ETC (non DSR - RA attached)	50.00	No	23.1	1155.00	INR One Thousand One Hundred & Fifty Five Only
21	P/ LAYING LIME CONCRETE M15 FOR PCC --ETC (non DSR - RA attached)	1.00	Cum	8927.286	8927.29	INR Eight Thousand Nine Hundred & Twenty Seven and Paise Twenty Nine Only
22	Providing and fixing 90 cm x 60 cm Granite plate engraving 10 cm. height letter, figures including painting the letters/figures with approved colour and shade complete SSR 18-19 ,44.12	2.00	No	10321.434	20642.87	INR Twenty Thousand Six Hundred & Forty Two and Paise Eighty Seven Only
23	Providing and fixing of water spout in Stone for draining of terrace water , As per Architectural Drawing and Design . Spout of Sizes Max . Length 900mm. As per market rate	4.00	Sqm	12000.00	48000.00	INR Forty Eight Thousand Only

24	Basalt stone Paving in lime Mortar - Providing and Laying Newasa Stone for paving and thread risers in cement mortar of 150 mm thick (Two line dressed stone 0.45x0.30x0.125 to 0.15 and not less than 0.30x0.30x0.15 Mtrs cut in shape and two adjacent sides Stone flooring in Basalt to be dressed, from Newasa, Dist Ahmednagar) in plain/diamond pattern on a bed of 1:4 C.M. over 150mm thick lime concrete , and filling the gap in 1:2 Mortar etc, complete) STONE DRESSING IN TICHIV STYLE Pune DSR 18-19 -14480 AK-63.27 , Page no.203)	10.00	Sqm	723.94	7239.40	INR Seven Thousand Two Hundred & Thirty Nine and Paise Forty Only
33	Landscaping work(Job work)	1.00	Lumsum	47908.33	47908.33	INR Forty Seven Thousand Nine Hundred & Eight and Paise Thirty Three Only
34	Testing Charges	1.00	Lumsum	65320.00	65320.00	INR Sixty Five Thousand Three Hundred & Twenty Only
35	Royalty Charges	1.00	Lumsum	9639.25	9639.25	INR Nine Thousand Six Hundred & Thirty Nine and Paise Twenty Five Only
Total in Figures					1719811.80	INR Seventeen Lakh Nineteen Thousand Eight Hundred & Eleven and Paise Eighty Only
Quoted Rate in Figures			Select		0.0000	INR Zero Only