

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority: CEO, ASCDCL , AURANGABAD

Name of Work: Conservation and Restoration of Roshan Gate

Contract No: ASCDCL/EE/WW/2019/ DATE

Bidder Name :						
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	CLEANING - Conveying materials obtained from road cutting including all lifts, laying in layers of 20cm to 30cm. breaking clods, dressing to the required lines, curves, grades and section, watering and compacting to not less than 97% of standard Proctor density for a lead of over 50m.to 300m. inclusive from the site of excavation to the site of deposition as directed. SSR 18-19 ,2.25	2.00	Cum	345.31	690.62	INR Six Hundred & Ninety and Paise Sixty Two Only
2	CAREFULLY REMOVAL OF GRASS, SCRAPING BRICK,STONE SURFACES BY CHEMICALS ,required oils and cleaning with jet spray etc --AS DIRECTED. (non DSR - RA attached)	655.00	Sqm	1129.20	739627.97	INR Seven Lakh Thirty Nine Thousand Six Hundred & Twenty Seven and Paise Ninety Six Only
3	Cutting down trees including trunks and branches with girths above 30cm to 60cm and stacking the materials neatly with all lifts and lead of 1000m as directed and earth filling in the depression / pit if any. SSR 18-19 ,2.01	3.00	No.	387.95	1163.84	INR One Thousand One Hundred & Sixty Three and Paise Eighty Four Only
4	Dismantling brick masonry in lime or cement mortar and stacking the materials as directed with all leads, lifts etc. SSR 18-19 ,46.09	4.38	Cum	455.40	1992.39	INR One Thousand Nine Hundred & Ninety Two and Paise Thirty Nine Only
5	P/C IST CLASS BRICK MASONRY [1:3] LIME MORTER WITH ORGANIC ADHESIVE-ETC (non DSR - RA attached)	4.38	Cum	8616.71	37698.10	INR Thirty Seven Thousand Six Hundred & Ninety Eight and Paise Ten Only
6	Dismantling stone masonry in lime or cement mortar including stacking the materials as directed with all leads, lifts etc. SSR 18-19 ,46.11	4.50	Cum	488.96	2200.30	INR Two Thousand Two Hundred and Paise Thirty Only
7	Scaling off deteriorated stone (non DSR - RA attached)	32.50	Sqm	483.00	15697.50	INR Fifteen Thousand Six Hundred & Ninety Seven and Paise Fifty Only
8	P/C UCR STONE MASONRY FOR SUPERSTRUCTURE [1:3] LIME MORTER WITH ORGANIC ADHESIVE--ETC (non DSR - RA attached)	11.00	Cum	5730.93	63040.23	INR Sixty Three Thousand & Forty and Paise Twenty Three Only
9	P/C IST CLASS COURSED/ASHLAR STONE MASONRY FOR SUPERSTRUCTURE [1:3] LIME MORTER WITH ORGANIC ADHESIVE--ETC (non DSR - RA attached)	13.50	Sqm	11081.13	149595.26	INR One Lakh Forty Nine Thousand Five Hundred & Ninety Five and Paise Twenty Five Only
10	Providing and applying Wacker Chemical (water base antifungal silicon treatment)on manglore tiles or stone surface. stone consolidation (Pune DSR 18-19 -14480 AK-63.15 -2 , Page no.203)	499.00	Sqm	503.28	251136.72	INR Two Lakh Fifty One Thousand One Hundred & Thirty Six and Paise Seventy Two Only
11	Removing the existing cement/lime plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. complete. SSR 18-19 ,32.33	286.84	Sqm	244.65	70176.70	INR Seventy Thousand One Hundred & Seventy Six and Paise Seventy Only

12	P/A 12 MM THK.LIME MORTER PLASTER[1:2] WITH ORGANIC ADHESIVE--ETC (non DSR - RA attached)	259.25	Sqm	757.5972	196407.07	INR One Lakh Ninety Six Thousand Four Hundred & Seven and Paise Seven Only
13	P/A 25 MM THK.LIME MORTER PLASTER[1:2] WITH ORGANIC ADHESIVE--ETC (non DSR - RA attached)	60.00	Sqm	1193.0724	71584.34	INR Seventy One Thousand Five Hundred & Eighty Four and Paise Thirty Four Only
14	TWO COATS LIME WASH PAINTING WITH NATURAL ORGANIC BINDERS--ETC. (non DSR - RA attached)	259.25	Sqm	622.65	161422.01	INR One Lakh Sixty One Thousand Four Hundred & Twenty Two and Paise One Only
15	P/A LIME MORTER [1:3] POINTING--ETC. (non DSR - RA attached)	499.00	Sqm	506.45	252717.85	INR Two Lakh Fifty Two Thousand Seven Hundred & Seventeen and Paise Eighty Five Only
16	Removing the tar or coba and disposing of the material as directed etc. complete. SSR 18-19 ,31.08	200.00	Sqm	125.17	25034.30	INR Twenty Five Thousand & Thirty Four and Paise Thirty Only
17	P/L WATERPROOFING TREATMENT USING BRICK BATS [1:2] LIME MORTER WITH ORGANIC BINDERS--ETC (non DSR - RA attached)	24.00	Cum	7274.94	174598.56	INR One Lakh Seventy Four Thousand Five Hundred & Ninety Eight and Paise Fifty Six Only
18	Excavation for foundation in earth, soils of all types, sand, gravel and soft murum, including removing the excavated material upto a distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift from 1.5m to 3.0m) By Mechanical Means SSR 18-19 ,21.04	113.13	Cum	392.49	44400.77	INR Forty Four Thousand Four Hundred and Paise Seventy Seven Only
19	Excavation for foundation in hard murum including removing the excavated material upto distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 SSR 18-19 ,21.06	6.00	Cum	370.47	2222.85	INR Two Thousand Two Hundred & Twenty Two and Paise Eighty Five Only
20	Providing antitermite treatment around the periphery of the existing building as per I.S. 6313 (Part-III) by excavating trenches of 20cm width and exposing the sides of columns and plinth beams upto a depth of 300mm and injecting one percent of chlorodane emulsion concentrate at the rate of 2.25 litres per Rmt and refilling the trenches etc. complete covering 2 years guarantee on bond paper. SSR 18-19 ,21.29	75.00	Rgm	50.33	3774.60	INR Three Thousand Seven Hundred & Seventy Four and Paise Sixty Only
21	Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete. SSR 18-19 ,21.38	31.88	Cum	1004.84	32029.39	INR Thirty Two Thousand & Twenty Nine and Paise Thirty Nine Only
22	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm including watering and compaction etc. complete. SSR 18-19 ,31.37	44.38	Cum	395.99	17572.18	INR Seventeen Thousand Five Hundred & Seventy Two and Paise Eighteen Only
23	P/ LAYING LIME CONCRETE M15 FOR PCC --ETC (non DSR - RA attached)	6.00	Cum	8927.29	53563.72	INR Fifty Three Thousand Five Hundred & Sixty Three and Paise Seventy Two Only

24	Basalt stone Paving in lime Mortar - Providing and Laying Newasa Stone for paving and thread risers in cement mortar of 150 mm thick (Two line dressed stone 0.45x0.30x0.125 to 0.15 and not less than 0.30x0.30x0.15 Mtrs cut in shape and two adjacent sides Stone flooring in Basalt to be dressed, from Newasa, Dist Ahmednagar) in plain/diamond pattern on a bed of 1:4 C.M. over 150mm thick lime concrete , and filling the gap in 1:2 Mortar etc, complete) STONE DRESSING IN TICHIV STYLE Pune DSR 18-19 -14480 AK-63.27 , Page no.203)	25.00	Sqm	7567.16	189179.04	INR One Lakh Eighty Nine Thousand One Hundred & Seventy Nine and Paise Four Only
25	GROUTING CRACKS,FILLING VOIDS AND FISSURES ON WALL WITH [1:2] LIME MORTER-ETC (non DSR - RA attached)	20.00	Sqm	433.08	8661.55	INR Eight Thousand Six Hundred & Sixty One and Paise Fifty Five Only
26	PROVIDING SOIL BAGS FOR SUPPORTS-- ETC (non DSR - RA attached)	100.00	No.	23.10	2310.00	INR Two Thousand Three Hundred & Ten Only
27	Stitching of cracks- Providing and fixing in position TMT FE 500, 32 mm dia dowel bars precoated with anticorrosive epoxy paint of required Dia. 60 cms. Long and at 30.00 cm. C/C and wherever directed including handling, straightening, necessary cutting supported by TMT FE 500, chairs with proper alignment by using properly designed assembly of Bulkheads lubricating half length with bituminous paint as directed etc. complete. SSR 18-19 ,5.14	5.00	Sqm	331.33	1656.63	INR One Thousand Six Hundred & Fifty Six and Paise Sixty Three Only
28	Providing and fixing of water spout in Stone for draining of terrace water , As per Architectural Drawing and Design . Spout of Sizes Max . Length 900mm. As per market rate	2.00	No.	12000.00	24000.00	INR Twenty Four Thousand Only
29	Providing and fixing mild steel grill gate as per the detailed drawing including hinges, locking arrangements and painting in three coats of oil paint of approved colour and shade etc. complete.(weight 18 kg. to 20 kg. Per Sq.m.) Spec.No.: As directed by Engineer- in-charge. SSR 18-19 ,23.09	6.00	Sqm	1541.30	9247.77	INR Nine Thousand Two Hundred & Forty Seven and Paise Seventy Seven Only
30	For Railing between existing poles:- Providing and fixing mild steel grill work for windows, ventilators etc. 20 kg/sqm as per drawing including fixtures, necessary welding and painting with one coats of anticorrosive paint and two coats of oil painting complete. SSR 18-19 ,40.01	114.00	Sqm	1539.20	175468.57	INR One Lakh Seventy Five Thousand Four Hundred & Sixty Eight and Paise Fifty Seven Only
31	Landscaping work(Job work)	1.00	Lumsum	277887.08	277887.08	INR Two Lakh Seventy Seven Thousand Eight Hundred & Eighty Seven and Paise Eight Only
32	Testing Charges	1.00	Lumsum	62920.00	62920.00	INR Sixty Two Thousand Nine Hundred & Twenty Only
33	Royalty Charges	1.00	Lumsum	21398.22	21398.22	INR Twenty One Thousand Three Hundred & Ninety Eight and Paise Twenty Two Only
Total in Figures					3141076.12	INR Thirty One Lakh Forty One Thousand & Seventy Six and Paise Twelve Only
Quoted Rate in Figures			Select		0.0000	INR Zero Only
Quoted Rate in Words			INR Zero Only			